

Notes:-

All Trees to be planted in accordance with BS 4043 : 1989 Transplanting Root Balled Trees.

Planting Operations

1. Each tree to shall be placed upright in the centre of the hole.
2. The trees shall be set at the nursery level with allowance for settlement and with roots spread evenly outwards and downwards and anchored as shown.
3. The pit is to to be backfilled after planting with topsoil.
4. The backfilling media is to be placed in layers not exceeding 150mm shaking the tree gently to ensure even distribution of soil between the roots and carefully consolidating each separate layer.
5. The trees are to be fertilized with 100gms Enmag slow release and watered at time of planting.
6. The trees should also be watered immediately following planting and during any dry period continuing longer than 3 days.
7. The trees should be planted no later than the end of February and within the planting season.

PLACES DIRECTORATE - ENVIRONMENT

Wigan Council

Wigan Council
Places Directorate
Environment
Infrastructure
PO Box 100
Wigan
WN1 3DS

Proposed Organics
Waste Transfer Station


Tree Pit Details

Drawn: AC

Date: Aug 2014

Drawing Number H/MTS/A/12

© Crown Copyright and database rights 2013
Ordnance Survey 100019578



Notes:-

All Trees to be planted in accordance with BS 4043 : 1989 Transplanting Root Balled Trees.

Planting Operations

1. Each tree to shall be placed upright in the centre of the hole.
2. The trees shall be set at the nursery level with allowance for settlement and with roots spread evenly outwards and downwards and staked as shown.
3. The pit is to to be backfilled after planting with topsoil.
4. The backfilling media is to be placed in layers not exceeding 150mm shaking the tree gently to ensure even distribution of soil between the roots and carefully consolidating each separate layer.
5. The trees are to be fertilized with 100gms Enmag slow release and watered at time of planting.
6. The trees should also be watered immediately following planting and during any dry period continuing longer than 3 days.
7. The trees should be planted no later than the end of February and within the planting season.

PLACES DIRECTORATE - ENVIRONMENT



Wigan Council
Places Directorate
Environment
Infrastructure
PO Box 100
Wigan
WN1 3DS

Proposed Organics
Waste Transfer Station

Tree Pit Details

Drawn: AC

Checked:

Date: Aug 2014

Scale: NTS

Drawing Number H/WTSA/11

© Crown Copyright and database rights 2013
Ordnance Survey 100019578